

1040029

12-17-87

API NUMBER 15-151-21,311-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NW, SEC. 10, T 29 S, R 15 W/EX

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Fincham Well # 1 B

Operator: Raymond Oil Company, Inc.

County Pratt 154.38

Name & Address P.O. Box 48788

Well Total Depth 4750 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:35 p.m. Day: 17 Month: 12 Year: 19 87

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4740' Perfs at 4200-4204'

1st plug sand back to 4150' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:10 p.m. Day: 17 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' with 5 sx cement on top with dump bailer.

2nd plug pumped down 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. of hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 200-600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOLCED

(If observed, observe this plugging.)

DATE 1-7-88

INV. NO. 19412

Signed Stephen J. Pfeifer (TECHNICIAN)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
DEC 27 1987
12-23-87