

To: 1 090878
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 151-22,158 -00-00
NE SW SW, SEC. 14, T 29 S, R 15
990 feet from S section line
4290 feet from E section line

11-22
TECHNICIAN'S PLUGGING REPORT
Operator License # 5004
Operator: Vincent Oil Corporation
Name
Address 125 N. Market, Ste. 1075
Wichita, KS 67202-1721

Lease Name Howell Well # 1-14
County Pratt 158.11
Well Total Depth 4865 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWO Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling License Number 5420
Address 401 E. Douglas, Ste. 500, Wichita, KS 67201-8848

Company to plug at: Hour: 9:10 a.m. Day: 22 Month: 11 Year: 19 97

Plugging proposal received from Judy
(company name) White & Ellis Drilling (phone) 316-263-1102

to fill hole with heavy mud and spot cement through drill pipe
1st plug at 4816' with 40 sx cement, 2nd plug at 900' with 50 sx cement,
3rd plug at 370' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 p.m. Day: 22 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 4816' with 40 sx cement,
2nd plug at 900' with 50 sx cement,
3rd plug at 370' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
(XXXX) did not observe this plugging.

DATE DEC 10 1997

Signed _____ (TECHNICIAN)

INV. NO. 49632