

To: 1040907 11-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,586 - 00-00
SE NE NE, SEC. 8, T 29 S, R 15 W/E
4290 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31529
Operator: Mike's Testing & Salvage, Inc.
Name & Address P.O. Box 209
Chase, KS 67524

Lease Name Kulka Farm Trust # 1
County Pratt
Well Total Depth 4860 157.95 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 3 Month: 11 Year: 19 94

Plugging proposal received from Vernon Duntz, Jr.

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 4859' w/200 sx cement, Perfs at 4697-4756'
1st plug sand back to 4650' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8'5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 3 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4650' and dumped 5 sx cement on top of
sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. 11-15-94
Maximum pressure 700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (or my representative) observe this plugging.

DATE 11-30-94
INV. NO. 41769

Signed Stephen J. Leffler
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1994
CONSERVATION DIVISION
WICHITA, KANSAS