

1090361

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,623-⁸⁰⁻⁰⁰

NE NE NE, SEC. 8, T 29 S, R 15 W/EX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Kulka Farm Trust Well # 2

Operator: Raymond Oil, Co., Inc.

County Pratt 156.78

Name & Address: One Main Place, Suite 900

Well Total Depth 4824 (Mississippi) feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 380

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 3:00 am Day: 19 Month: June Year: 19 85

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 819-40' Elevation 2000'

1st plug at 840' with 50 sx cement

2nd plug at 420' with 40 sx cement

3rd plug solid bridge
hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement.
Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 am Day: 19 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement, 2nd plug at 420' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

6-21-85

JUN 21 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-25-85

Signed Robert B. Tarbutton
(TECHNICIAN)

INV. NO. 8680

6-19