

1 050640

API NUMBER 15-151-21,705-00-00

To: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION approx SW NW, SE SEC. 8, T 29 S, R 15 (W) 200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

1720 feet from S section line 2240 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Bryant "C" Well # 8

Operator: TXO Production Corp.

County Pratt 160.88

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 4950 Arbuckle feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldabaran Drilling Co Inc. License Number 5829

Address 453 S. Webb Road Suite 100 Wichita KS. 67207

Company to plug at: Hour: 4:15 am Day: 11 Month: October Year: 19 85

Plugging proposal received from Scott Mason

(company name) Aldabaran Drilling Co. (phone) 316-672-7471

work: To spot plugs through drill pipe at determined depths. Also keep hole full of good quality mud at all times. Anhydrite was at 960'

1st plug at the top of the arbuckle with 50 sx cement

2nd plug at the base of the anhydrite with 50 sx cement

3rd plug at 330' with 50 sx of cement 4th plug at 40' with a solid bridge and 10 sx

5th and 6th plugs circulate Rat hole and mouse hole with 10 sx of cement each.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:00am Day: 11 Month: October Year: 19 85

ACTUAL PLUGGING REPORT All plugs spotted through drill pipe.

1st plug at 94900' with 50 sx of cement

2nd plug at 970' with 50 sx of cement 10-28-85

3rd plug at 380' with 50 sx of cement

4th plug at 40' with a solid bridge and 10 sx of cement to the top RECEIVED STATE CORPORATION COMMISSION

5th and 6th plugs circulate rat hole and mousehole with 10 sx of cement each OCT 28 1985

Remarks: Cement used was 60/40 pozmix 6% gel pumped by B J Titan CONSERVATION DIVISION Wichita, Kansas (If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE OCT 29 1985

Signed Richard W. Lacey (TECHNICIAN) P.A.S.

INV. NO. 10759