

6-17-87

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,838 - 00-00
NW SW NW, SEC. 16, T 29 S, R 15 W/E
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name & Address
P.O. Box 48788
Wichita, KS 67201

Lease Name Perdue Well # 1 "A"
County Pratt 159.32
Well Total Depth 4902 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling License Number 5929
Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 8:15 a.m. Day: 17 Month: 6 Year: 19 87

Plugging proposal received from John Armbruster
(company name) Duke Drilling (phone) 316-267-1331
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2027'
Anhydrite 930'

- 1st plug at Arbuckle less 50' with 50 sx cement,
- 2nd plug at Anhydrite with 50 sx cement,
- 3rd plug at 360' with 50 sx cement, 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 10 a.m. Day: 17 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement,
2nd plug at 370' with 50 sx cement,
3rd plug at 40' with Solid Bridge Plug and 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

6-19-87
RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to) observe this plugging.

DATE 6-22-87
INV. NO. 17294

Signed Richard W. Lacey
(TECHNICIAN)