



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 15 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Allen Oil Co

Complete Address Box 339 Great Bend, KS

Lease Name Tregallas Well No. 6

Location C W/2 SE/NE Sec. 32 Twp. 26 Rge. 13 (E) (W)

County Pratt Total Depth 4290

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 3:00 PM Day 13 Month 1 Year 1975

The above well was plugged as follows:

850 ft 9 5/8 surface cemented with 400 sacks. 4279 ft 5 1/2 long string  
cemented with 200 sacks. Open hole. Sand to 4250 ft, 5 sacks cement  
with bailer. Pulled 2830 ft 5 1/2. Set 10 ft rock bridge at 280 ft.  
Fill hole with 4 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed [Signature]  
Plugging Supervisor

INVOICED  
DATE 1/15/75  
INV. NO. 642-W