

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR RAMA Operating Co., Inc.

ADDRESS Box 159 Stafford, KS 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom T.D. 3995'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	247'	none
				5 1/2	3998'	2208'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set. Sanded bottom @ 3750' & dumped 5 sks cement. Shot @ 2800, 2600, 2500, 2400 & 2208. Came loose @ 2208'. Plugged well with 300# hulls, 10 gel, 50 sks cement, 10 gel, 100# hulls, release plug, 125 sks cement. 60/40 pos 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (Employee of Operator) of         

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19 94

Irene Herzberg  
 Notary Public

My Commission Expires:         

