

15-185-11307-0001

STATE OF KANSAS
CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR King & Rowe Oil

ADDRESS 2400 White Sands Drive
Great Bend, Kansas 67530

PHONE (316) 792-2756 OPERATORS LICENSE NO. _____

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3888 $\frac{1}{2}$ '

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	297'	none
				5-1/2"	3999'	813'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3300' and 5 sacks cement. Shot pipe @3200', 3000', 2800', 2700', 2600', pipe parted @813', pulled a total of 27 joints of 5-1/2" casing. Plugged surface with 4 sacks hulls and 150 sacks econolite.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1987

My Commission Expires: 12-30-87



CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-86

12-30-87

Owner: A. S. Ritchie, et al
 Operators: D. R. M. Company
 Lease & Well: Richardson Well #1
 Locations: NE $\frac{1}{4}$ SW $\frac{1}{4}$ 22-24-11 - Stafford County, Kansas
 Commenced: January 5, 1943.
 Completed: January 27, 1943
 Casing: Surface casing at 297' Cemented W/ 175 sacks
 3888' of 5 $\frac{1}{2}$ " casing Cemented W/ 100 sacks

LOG

Clay	70
Sand	130
Red rock	150
Shale	750
Shale & shells	1400
Broken lime	2670
Lime	2765
Broken lime	2970
Lime	3235
Broken lime	3320
Lime	3375
Shale	3455
Lime	3519
Broken lime	3542
Lime	3581
Lime soft	3595
Lime med soft	3610
Lime	3740
Shale	3822
Coring	3828
Ream core hole	3828
Lime	3832
Cored	3839
Reamed	3839
Lime	3850
Cored	3856
Lime	3888
	} T. D.

Please note - This Richardson oil lease was recently purchased from Ritchie Exploration, Inc. (operator Lic. #4767), and we haven't received the Well files yet. I called their Geologist - Galen Babcock, and he sent me a copy of this old well log.

I've done the best I can with it as this application - hopefully it's sufficient, otherwise we'll have to go to "Ritchie's Well files".

Thank you!
 Ron Rowe

8-18-87

RECEIVED
 STATE CORPORATION COMMISSION

AUG 18 1987

CONSERVATION DIVISION
 Wichita, Kansas