

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1966
7-26-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Calbeck Well No. # 6

Location NE NE NE Sec. 33 Twp. 26 Rge. 13 (X) (W) W

County Pratt Total Depth 4426'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:30 Day 23rd Month July Year 1966

The Above well was plugged as follows:

798' of 10 3/4" surface pipe, cemented with 775 sacks. 4401' of 7" long string,
cemented with 200 sacks. Plug back T.D. 4372'. Top perforation 4302'. Bottom of
the hole was sanded to 4290', and cemented with 7 sacks, through the dump bail-
er. 3088' of 7" long string was recoered from the hole. Bridge plug was pushed
in fluid to 325', rock bridge from 325' to 315'. 6 sacks of cement was mixed in
a barrel, and put on plug at 315', through the dump bailer, and let set over-
night. Hole was bailed dry, and 24 sacks of cement was added to the plug. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented with 15
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/26/66

INV. NO. 3621-W