

11
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1963
11-15-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name McAdams Pipe & Supply Co.

Complete Address: 2700 N. Main, Great Bend, Kansas

Lease Name Lemon Well No. # 3

Location NE NE SE Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4470

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 5:30PM Day 11th Month Nov. Year 1963

The Above well was plugged as follows:

860' of 8 5/8" surface pipe, cemented to top. 4469' of 5 1/2" long string,
cemented with 75 sacks. Bottom of hole was sanded to 4400', and cemented
with 5 sacks. Hole was bailed down. Plug and 10' rock bridge was set at
300', cemented with 25 sacks. Hole was filled with mud to 40', 10' rock
bridge, cemented with 10 sacks to base cellar.
3227' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 11/15/63
INV. NO. 8106-W

Signed: Archie Elving
Well Plugging Supervisor

INVOLCED