

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAR 10 1964  
3-10-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name R. W. Rine Drilling Co.

Complete Address: Box 452, Pratt, Kansas

Lease Name Jo Well No. # 3

Location NE NW SW Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4483

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:00PM Day 8th Month March Year 1964

The Above well was plugged as follows:

848' of 8 5/8" surface pipe, cemented with 400 sacks. 4480' of 5 1/2"  
long string, cemented with 250 sacks. Plug back to 4449'. Top perfor-  
ation 4182'. Bottom of hole was sanded to 4150', and cemented with 5  
sacks. Fluid in the hole was bailed down to 300'. Plug was set at 300',  
with 10' rock bridge, and cemented with 25 sacks. Hole was filled with  
mud to 40', with 10' rock bridge, and cemented with 10 sacks to base  
cellar.

3150' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3/10/64  
INV. NO. 8756-W