

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-10-75
JAN 10 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C.H. Todd Inc

Complete Address Box 925 Great Bend, KS

Lease Name Joe Well No. 1

Location SW/SW/SW Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4439

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 1:00 PM Day 8 Month 1 Year 1975

The above well was plugged as follows:

326 ft 8 5/8 surface cement circulated. 4439 ft 5 1/2 long string
cemented with 250 sacks. Top perf. 4254 ft. Sand to 4200 ft, 5
sacks cement with bailer. Pulled 2150 ft 5 1/2. Pump 3 hulls, 15 gel,
100 sacks cement to surface.

Pumped by Halliburton Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed Russell B. Bickert
Well Plugging Supervisor

DATE 1/10/75

INV. NO. 633-W