

KANSAS

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966
6-20-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Karl Strait Well No. # 7

Location SE SW NW Sec. 33 Twp. 26 Rge. 13 (E) W

County Pratt Total Depth 4457'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:45 PM Day 18th Month June Year 1966

The Above well was plugged as follows:

854' of 8 5/8" surface pipe, cemented with 369 sacks. 4452' of 5 1/2" long
string, cemented with 250 sacks. Plug back T.D. 4416'. Top perforation
4298'. Bottom of the hole was sanded to 4275', and cemented with 5 sacks,
through the dump bailer. 3236' of 5 1/2" long string was recovered from the
hole. Bridge plug was pushed in fluid to 300', rock bridge from 300' to
290'. 5 sacks of cement was mixed in a barrel and put on plug at 290',
through the dump bailer, and let set over-night. Next day hole was bailed
dry and 20 sacks of cement was added. Hole was filled with mud to 40',
and cemented with 10 sacks to the base of the cellar..

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/20/66
INV. NO. 3423-U

Signed: Archie Elving
Well Plugging Supervisor