

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1966
7-1-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Karl Strait Well No. # 8

Location SE SE NW Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4474'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 2:00PM Day 28th Month June Year 1966

The Above well was plugged as follows:

665' of 8 5/8" surface pipe, cemented with 340 sacks. 4470' of 5 1/2" long
string, cemented with 275 sacks. Plug back T.D. 4432'. Top perforation 4284'.
Bottom of the hole was sanded to 4275', and cemented with 5 sacks, through
the dump bailer. 2919' of 5 1/2" long string was recovered from the hole.
Bridge plug was pushed in fluid to 325', rock bridge from 325 to 315'. 5 sac-
ks of cement was mixed in a barrel, and put on plug at 315', through the
dump bailer, and let set for days. Hole was bailed dry and 20 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/1/66
INV. NO. 3491-W