

Form CP-3  
Rev. 6-26-62

~~16~~ KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

11-18-63  
**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 18 1963  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name McAdams Pipe & Supply Co.

Complete Address: 2700 N. Main, Great Bend, Kansas

Lease Name Lemon Well No. # 2

Location NW NE SE Sec. 33 Twp. 26 Rge. 13 (E) (W)W

County Pratt Total Depth 4468

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 3:00PM Day 15th Month Nov. Year 1963

The Above well was plugged as follows:

848' of 8 5/8" surface pipe. 4466' of 5 1/2" long string. Bottom of hole  
was sanded to 4450', and cemented with 5 sacks. Hole was bailed down,  
and plug was set at 300', 10' rock bridge, cemented with 25 sacks.  
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks  
to base cellar.  
3116' of 5 1/2" long string was recovered from the hole.

I hereby certify that the (above) well was plugged as herein stated.

DATE 11/18/63  
INV. NO. 8119-W

Signed: Archie Elving  
Well Plugging Supervisor