

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUL 19 1966
7-19-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
300 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Calbeck Well No. # 8

Location SW SE NE Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4434'

Abandoned Oil Well Gas Well Input Well STD Well B & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 1:30AM Day 14th Month July Year 1966

The Above well was plugged as follows:

447' of 8 5/8" surface pipe, cemented with 250 sacks. 4430' of 5 1/2" long string, cemented with 220 sacks. This is an open hole. Bottom of the hole was sanded to 4400', and cemented with 5 sacks, through the dump bailer. 3200' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 325', rock bridge from 325' to 315'. 8 sacks of cement was mixed in a barrel, and put on plug at 315', and let set for days. Hole was bailed dry, and 17 sacks was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/19/66
INV. NO. 3591-u