

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUL 19 1966
7-19-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
300 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Calbeck Well No. # 14

Location SE SW NE Sec. 33 Twp. 26 Rge. 13 (E) (W)

County Pratt Total Depth 4468'

Abandoned Oil Well X Gas Well Input Well STD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 3:30PM Day 14th Month July Year 1966

The Above well was plugged as follows:

838' of 8 5/8" surface pipe, cemented with 340 sacks. 4466' of 5 1/2" long string, cemented with 250 sacks. Plug back T.D. 4320'. Top perforation 4309'. Bottom of hole was sanded to 4300', and cemented with 5 sacks, through the dump bailer. 3160' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 325', rock bridge from 325' to 315'. 5 sacks of cement was mixed in a barrel, and put on plug at 315, through the dump bailer, and let set for days. Hole was bailed dry and 20 sacks of cement was added to the plug, Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/19/66
INV. NO. 3592-W