

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 112-17

LOCATION S1-21E-21E

SEC. 25 TWP. 26 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Louis Kugh

Operator Mid-Continent P.T. Corp. Address 512 Osborn Bldg. Wichita-Kans

Field \_\_\_\_\_ County Reott

Total Depth 4333 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 448 ft. Circulated with cement.  
5 1/2" casing set at 4316 ft. 250 sacks of cement - same Wells  
Plug at 3939 ft. - Plug set back at 3860 ft with chat-  
filled off & pulled thru 5 1/2" casing - Mixed 5 sacks of  
Cement at 3860 ft - mud to 250 ft - Set 4 inch bridge  
& 15 sacks of cement at 250 ft - mud to 35 ft -  
Bridge & 10 sacks of cement at the surface.  
Bill Morgan - Plugging Contractor

RE  
STATE CORPORATION

NOV - 8 1951

CONSERVATION DIVISION  
Wichita, Kansas

C. H. Stough  
District Conservation Agent

Date 11-4-51

**PLUGGING**  
FILE SEC 257 26 R13W  
BOOK PAGE 112 LINE 17