

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217


FORM CP-4

WELL PLUGGING RECORD

Stafford County, Sec. 22 Twp. 24 Rge. (E) 11 (W)

Location as "NE/CNW/SE/SW" or footage from lines CNL NW NE
Lease Owner Santa Fe Pipe & Supply, Inc.
Lease Name McComb Well No. 3
Office Address Box 562, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed Dec. 5 1941
Application for plugging filed Nov. 28 1975
Application for plugging approved _____ 19____
Plugging commenced Dec. 4 1975
Plugging completed Dec. 8 1975
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3870 feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			279'	8 5/8"	279'	none
			3799'	1 1/2"	3799'	1600.12

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3700' and dumped 4 sacks of cement.

Halliburton plugged well pumping in 2 sacks of hulls, 10 sacks of gel and 100 sacks of cement.

RECEIVED
STATE CORPORATION
DEC 11 1975

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 128, Ellinwood, Kansas 67526

CONSERVATION
WICHITA

STATE OF KANSAS COUNTY OF BARTON SS.
Evelyn Roth (employee of owner) or (owner-operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1975

My commission expires _____
JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

Jenny Kasselman
Notary Public.


15-185-11273-0000

DASA OIL CO.
McCombs No. 3.

SEC. 22 T. 24 R. 11 W.
CNL NW NE

Total Depth. 3814 1/2'
Comm. 11-8-41 Comp. 12-5-41
Shot or Treated.
Contractor. Creekmore Drlg. Co.
Issued. 1-31-42

County. Stafford



CASING:
8 5/8" 279'
4 1/2" 3799' Com.

Elevation.

Production. Pot. 2940 B. Bmb

Figures Indicate Bottom of Formations.

sand & shells	125
shale, sand, red rock	285
red rock	545
anhydrite	575
shale & shells	995
shale & salt	1405
shale & lime	1590
lime	1825
lime brkn	1945
shale & shells	2040
shale & lime	2165
shale & shells	2270
shale	2375
shale & shells	2455
shale	2600
shale & shells	2835
shale	2905
lime	2920
shale & lime	2985
lime	3245
shale & lime shells	3315
shale & lime	3340
shale	3410
lime brkn	3475
lime	3605
shale & lime	3660
lime brkn & shale	3700
lime	3714
shale & lime	3756
shale	3801
lime chert	3803
lime oil & gas	3814 1/2
Total Depth.	

sh oil 3420-25
oil odor in samples 3440

Tops: Lansing 3410
Misener 3799

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1975

124-75

CONSERVATION DIVISION
Wichita, Kansas

Producer