

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Stafford

County. Sec..... Twp..... Rge..... (E).....(W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

Lease Owner Crown Oil Company

Lease Name Newell Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed.....19.....

Application for plugging filed.....19.....

Application for plugging approved.....19.....

Plugging commenced.....May 2, 1949.....19.....

Plugging completed..... May 4, 1949..... 19.....

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... C. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Pumped mud in hole to kill gas and water.
Mudded hole to 276'. Set rock bridge to 261'.
Run 15 sacks of cement. Mudded hole to 40'. Run 10 sacks
of cement. Filled hole to top. Well Completed.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....
.....
.....

STATE OF KANSAS, COUNTY OF BARTON, ss.
E. M. Hilton (employee ☒ or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God.

(Signature)


Odell & 10th St., Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of May, 1949

My commission expires.....June 13, 1951.

22-5133-S

9-48-10M



MAY 12 1949 5-12-49
STATE CORPORATION
COMMISSION
KANSAS

D R I L L E R ' S L O G

COMPANY: FRANK W. FREDERICKS, ET AL LOCATION: SE SW 21-24-11W
CROWN OIL COMPANY, INC. Stafford, County,
Kansas
CONTRACTOR: CROWN OIL COMPANY, INC.
FARM NAME: No. 1 NEWELL ELEVATION: 1817
COMMENCED: 3-25-49
COMPLETED: 4-13-49

CASING USED: 8-5/8" at 276' with 200 sacks
5-1/2" at 3834'

Cellar	4
Surface Clay	35
Sand	113
Clay and Shells	165
Red Bed	215
Sand	245
Red Bed, Shells	276
Red Bed Shells	580
Lime	600
Red Bed	810
Blue Shale	990
Shale and Shells	1305
Salt - Shale	1520
Shale and Shells	1630
Anhydrite Gyp & Shale	1735
Lime and Shale	1935
Lime and Shale Breaks	2015
Lime and Shale	2075
Lime	2130
Lime and Shale	2220
Lime and Shale Broken	2370
Shale and Shells	2715
Broken Lime	2780
Shale	2936
Lime Broken	2985
Shale and Lime	3175
Shale	3215
Lime	3245
Shale and Shells	3300
Lime and Shale	3440
Lime	3707
Lime and Shale	3815
Lime Shale Cherty	3830
Lime Cherty	3848
Lime	3865
Total Depth	3865

GEOLOGICAL TOPS:

Lansing (White)	3440	-1623
Base KC (Questionable)	3704	
Penn. Detrital	3762	
Kinderhook Weathered		
Material	3784	
Viola (Cherty)	3834	-2017

5-12-49

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, the undersigned, being duly sworn on oath state that the above statement and log is true and a correct record and log of the well drilled at the location above-described.

CROWN OIL COMPANY, INC.

By Sam R. Hilton
Secretary

Subscribed and sworn to before me this 29th day of April, 1949.

Henry Peacock
Notary Public

My Commission expires June 13, 1951

