

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202
KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 515-185-22184-0000

LEASE NAME BAUER

WELL NUMBER #1

3620 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 21 TWP. 24 RGE. 11 (X) or (W)

COUNTY STAFFORD

Date Well Completed JUNE 1985

Plugging Commenced 11/26/99

Plugging Completed 12/1/99

DEC 07 1999
12-7-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION

WICHITA, KS

LEASE OPERATOR WOOLSEY PETROLEUM CORPORATION

ADDRESS 1966 SE RODEO DRIVE RD. P.O. BOX 168

PHONE# (316) 886-5606 OPERATORS LICENSE NO. 5506

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 17/18/99 (date)

by N/A (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation MISSISSIPPI Depth to Top 3828' Bottom 3888' T.D. 4074'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
VIOLA	OIL & WATER	SURFACE	257'	8 5/8"	257'	-0-
		SURFACE	4076'	5 1/2"	4076'	1666'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. SAND BACK TO 3500'. PLACE 5 SX CMT ON TOP OF SAND. CUT & PULL 1660' CASING. FROM SURFACE DOWN 8 5/8" CASING PUMP 300# COTTON SEED HULLS, 10 SX GEL, 50 SX 60/40 CMT, 10 SX GEL, 100# COTTON HULLS, 8 5/8" WIPER PLUG, 125 SX 60/40 CMT.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING CO. License No.

Address MEDICINE LODGE, KS. 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOOLSEY PETROLEUM CORPORATION


STATE OF KANSAS COUNTY OF BARBER, ss.

CARL W. DURR

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address)



SUBSCRIBED AND SWORN to before me this 6 day of December, 19 99

Carla M. Capansky
Notary Public

My Commission Expires: 11/17/2002