

**STATE OF KANSAS
STATE CORPORATION COMMISSION**

**Get All Information Completely
Make Required Affidavit
Mail or Deliver Report to:**
**Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

			X

Locate well correctly on above
Section Plat

Stafford

County. Sec. 20 Twp. 24 Rge. (E) 11 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330'

Lease Owner..... J. C. Shaffer, Inc.

Lease Name Newell

Office Address 913 Ramsey Tower - Oklahoma City, Oklahoma

Character of Well (Completed as Oil, Gas or Dry Hole)..... Dry Hole

Date, well completed February 4, 1938

Application for plugging filed February 6, 1938

Application for plugging approved.....	193
--	-----

Plugging Commenced February 6, 1938

Plugging Completed..... February 6, 1938

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production.....193

Was permission obtained from the Conservation Division or its agents before plugging was commenced?
Yes

Name of Conservation Agent who supervised plugging of this well.....C. T. Alexander

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4084 Feet.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS



CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"OD	332'	NONE
Copy of log attached.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole filled with mud laden fluid.

Cement plug from 332' up to 300' and from 15' to surface.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. C. Shaffer, Inc.

Address..... 913 Ramsey Tower
Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described
well as filed and that the same are true and correct. So help me God.

(Signature) _____

913 Ramsey Tower, Oklahoma City, Okla.

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 1938.

My commission expires Nov. 27, 1939.

17-932 9-37-5M

Notary Public.

WELL LOG

Newell #1 - NE/4-NE/4-SE/4, Section 20-24S-11W - Stafford County, Kansas.

Operator - J. C. Shaffer, Inc. - 913 Ramsey Tower, Oklahoma City, Okla.

Contractor- J. C. Shaffer, Inc.- 913 Ramsey Tower, Oklahoma City, Okla.

Date Drilling Commenced - January 11, 1938.

Date Drilling Completed - February 4, 1938.

Total Depth - 4084 ft.

Dry and Abandoned.

NATURE OF FORMATIONS

Surface & Sand	to	110'	
Sand		312	
Red Bed		332	- Set 10" Surface Casing.
Red Bed		590	
Shale & Shells		760	
Shale		925	
Shale & Shells		1080	
Shale		1125	
Salt		1305	
Salt & Shale		1470	
Lime Shells		1480	
Lime & Shale		1590	
Anhydrite		1630	
Broken Anhydrite & Shale		1690	
Shale & Lime		1900	
Sand		1925	
Shale & Lime		1935	
Shale & Shells		1985	
Lime		2030	
Shale & Lime		2790	
Lime		2805	
Lime & Shale		2920	
Sand		2960	
Shale & Lime		2980	
Lime		3275	
Shale & Lime		3325	
Sandy Shale & Lime		3390	
Shale & Lime		3455	- Top Lansing Lime 3460'.
Lime		3610	
Lime & Shale		3650	
Lime		3780	
Broken Shale		3805	- Top Conglomerate 3840'.
Shale		3900	- Cored 3845-3852, Recovered 3" Chirt.
Lime & Shale		3925	- Cored 3852-3868, Rec. 15' Green Shale.
Lime		3933	- Top Viola 3892'. (Kinderhook)
Lime & Chirt		3945	- Top Simpson 3990'.
Lime		4005	
Sand & Shale		4020	- Cored 4050-4066, Rec. 15' Simpson Green Shale, 1 1/2' White Sugary Silicious Dolomite, Porous.
Shale		4065	- Top Silicious Lime
Lime - Silicious		4084	- T.D. - 4066 1/2-4084 Cored. Recovered 8' Silicious Lime.

*Rec'd
2-10-38*

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

J. C. Shaffer

Sec.-Treas.

Subscribed and sworn to before me this 9th day of February, 1938.

My Commission expires November 27, 1939.

James Dickert
Notary Public