


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, Sec. 21 Twp. 26S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines. SW SW SE
Lease Owner R. W. Rine Drilling Company
Lease Name Frisbie "B" Well No. 1
Office Address 320 Central Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed MAY 9, 1953 19
Application for plugging filed JUNE 30, 1953 19
Application for plugging approved JUNE 30, 1953 19
Plugging commenced July 1 1953
Plugging completed July 6 1953
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	880'	None
				5-1/2"	4390'	3069'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 4360' to 4260' and ran 5 sacks of cement. Mudded hole to 300', set 10' rock bridge and ran 20 sacks of cement. Mudded hole to 35', set rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. H. SLOYER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STATE CORPORATION COMMISSION (Signature) E. H. Sloyer

JUL 13 1953 7-13-53 320 CENTRAL BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this JULY 19 53
Wichita, Kansas

My commission expires December 29, 1956 Notary Public.



SW SW SE
SECTION 21-26S-13W
PRATT COUNTY, KANSAS

FRISBIE "B" WELL NO. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
STARTED: 4-28-53 FINISHED: 5-9-53

LOG

WASHED OUT HOLE
PLUGGED BACK W/50 SX. CEMENT,
AND WHIPSTOCKED W/KNUCKLE JOINT
AT 3560'

0 - 3654 TOP OF 5 1/2" CASING IN DRY HOLE WHICH
IRON DRILLING COMPANY DRILLED IN OCTOBER,
1951. SYFO @ 3654' - OK

LIME	3610 - 3640	SYFO @ 3632' - 6 1/2'
LIME AND SHALE	3640 - 3820	SYFO @ 3800' - 3 1/2'
LIME	3820 - 3860	
LIME AND SHALE	3860 - 3963	
LIME	3963 - 4200	SYFO @ 4110' - 2-3/4'
LIME AND SHALE	4200 - 4235	
LIME	4235 - 4300	
CHERTY LIME	4300 - 4345	
CHERT & LIME	4345 - 4370	SYFO @ 4370 - 1 1/2'
LIME AND SHALE	4370 - 4391	T.D. - 5 1/2" CASING @ 4391' W/200 SACKS POSMIX

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE FRISBIE "B" WELL NO. 1, LOCATED IN THE SW SW SE, SECTION 21-26S-13W, PRATT COUNTY, KANSAS.


ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 19TH DAY OF MAY, 1953.


NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955.

PLUGGING
MAY 26 1953
COOK

STATE OF KANSAS
JULY 1953
CONSERVATION DIVISION
Wichita, Kansas