


15151-00318,00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County, Sec. 24 Twp. 26S Rge. 13 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner National Cooperative Refinery Association  
Lease Name Gobin Well No. 1  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 1, 1955  
Application for plugging filed October 3, 1955  
Application for plugging approved October 5, 1955  
Plugging commenced October 1, 1955  
Plugging completed October 1, 1955  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4511 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	376'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 300', set plug, deumped 20 sax of cement. Mudded hole to 35', set plug, dumped 10 sax cement on up to bease of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor M. B. Armer  
Address Petroleum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) C. R. Sears C. R. Sears  
305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1955

My commission expires June 30, 1958

C. Orville May Notary Public.

**PLUGGING**  
FILE SEC. 24-26-R/34  
BOOK PAGE 6 LINE 4

RECEIVED  
C. Orville May  
Rec'd  
OCT 7 1955  
10-7-55  
CONSERVATION DIVISION  
Wichita, Kansas

**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H. B. Armor Co. H.C.R.A.

SEC. 24 T. 26 R. 13W

FARM Gobin No. 1

LOC. SE 5' 11'

TOTAL DEPTH 4511'

COUNTY Pratt

COMM. 9/15/55


COMP. 10/1/55

KANSAS

SHOT OR TREATED

CONTRACTOR H. B. Armor

ISSUED



CASING

20	10	
15	8	382
12	6	
13	5	

ELEVATION 1938 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Shale	105
Sand & Shale Streaks	160
Sandy Shale	330
Red Bed & Shells	376
Shale, Sand & Shells	795
Anhydrite	810
Shale & Shells	1215
Shale, Shells & Salt	1595
Shale & Lime	1885
Shale & Lime Shells	2040
Shale & Lime	3365
Lime	3435
Lime & Shale	3520
Lime	3588
Lime & Shale	3910
Lime	3945
Shale & Lime	4050
Lime	4089
Lime & Shale	4218
Cherty Lime	4240
Lime & Chert	4250
Lime & Shale	4280
Cherty Lime	4290
Lime & Shale	4330
Shale & Cherty Lime	4401
Cherty & Sandy Lime	4431
Shale	4478
Shale & Lime	4511

FORMATION TOPS

HENDER	3597
DOUGLASS SAND	3658
BROWN LIMES	3763
LANING	3786
BASE KANSAS CITY	4107
PARMATION CHERT	4151
ILLINOISSIAN PI	4232
KINDERHOOK	4299
VIOLA	4325
SEMPSON	4376
ARBUCKLE	4488

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H. B. ARMOR

By *C. P. Sprouling*

STATE OF KANSAS |  
 |  
 COUNTY OF SEDGWICK | SS:

Subscribed and sworn to before me, a notary public, in and for said County and State this 3rd day of October, 1955.

**PLUGGING**  
 FILE SEC 24 T 26 R 13W  
 BOOK PAGE 6 LINE 4

*Noise Furey*  
 Notary Public

My Commission expires February 13, 1956.

NOTARIAL DIVISION  
 WICHITA, KANSAS