


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

PRATT County. Sec. ²⁴~~25~~ Twp 26 Rge 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines C W/2 SE SW
Lease Owner SANTA-FE PIPE & SUPPLY, INC
Lease Name GOBIN Well No. 2
Office Address BOX 562, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed JULY 31 19 55
Application for plugging filed JULY 18 19 66
Application for plugging approved JULY 25 19 66
Plugging commenced AUGUST 4 19 66
Plugging completed AUGUST 11 19 66
Reason for abandonment of well or producing formation DEPLETED



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	465	NONE
				5 1/2"	4378	3619

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 4378 - 4175 - SAND
- 4175 - 4115 - 5 SACKS CEMENT
- 4115 - 325 - MUD
- 325 - 315 - ROCK BRIDGE
- 315 - 300 - 5 SACKS CEMENT
- 300 - 240 - 20 SACKS CEMENT
- 240 - 40 - MUD
- 40 - 30 - ROCK BRIDGE
- 30 - BASE- 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1966
9-30-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T.L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.L. Nutt
BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 20TH day of SEPTEMBER, 19 66,
Mary M. Guzman
Notary Public.

My commission expires JULY 31, 1970


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. MCKNAB DRILLING, INC.
Farm. Gobin No. 2

SEC. 24 T. 26 R. 13W
C W/2 SE SW

Total Depth. 4378
Comm. 7-11-55 Comp. 7-31-55
Shot or Treated.
Contractor.
Issued. 12-24-55

County Pratt
KANSAS



Elevation. 1938 RB

Production. 105 BOPD

CASING:
8 5/8 465' w/ 325 sx cmt.
5 1/2 4378' w/ 150 sx cmt.

Figures indicate Bottom of Formations

sand & shale	300
red bed	415
shale & shells	1200
lime & shale	1875
lime	2240
shale & lime	2795
shale	2980
shale & lime	3500
shale	3655
lime & shale	3739
lime	4124
chert & lime	4167
lime	4240
lime & sand	4263
sand & shale	4283
shale	4336
Arbuckle lime	4338
Core #1:	4356
Core #2:	4376
Core #3:	4378
Reaming	4336-4345
Reaming	4345-4378
Total Depth	

SCOUT TOPS:	
Heebner	3546
Brown lime	3706
Lansing	3738
Base K. C.	4060
Mississippi	4149
Kinderhook	4162
Viola	4188
Simpson	4232
Arbuckle	4336

Ran Schlumberger E. L.

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1966
CONSERVATION DIVISION
Wichita, Kansas