

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,462 -00-00

LEASE NAME Griffith

WELL NUMBER 1

SPOT LOCATION SW SW NW

SEC. 14 TWP. 26 RGE. 13 (X) or (W)

COUNTY Pratt

Date Well Completed 7-30-84

Plugging Commenced 7-30-84

Plugging Completed 7-30-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Roxana Corporation

ADDRESS P.O. Box 1850 Great Bend, KS 67530

PHONE # (316) 792-1383 OPERATORS LICENSE NO. 6283

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Mr. Lacy
to be filed by

Is ACO-1 filed? operator if not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4418

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 810' w/50 sacks 60/40 pozmix 2% gel 3% cc. thru drill pipe

Next Plug: @ 330' w/40

Top Plug: @ 40' w/Bridge plug and 10 sack cement

15 sacks cement in Rat hole

5 sacks cement in water well

(If additional description is necessary, use BACK of this form.)

STATE OF Kansas COUNTY OF Barton, ss.

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

~~XXXXXXXXXX~~ Ervin Neighbors (employee of operator) or

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, stated and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

AUG 06 1984
8-6-84
CONSERVATION DIVISION

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 2 day of August, 1984

Randy M. Hogue
Notary Public

My Commission expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: July 23, 1984
DATE COMPLETED: July 30, 1984

The Roxana Corporation
GRIFFITH #1
SW SW NW
Sec. 14, T26S, R13W
Pratt County, Ks.

0 - 788' Surface Soil, Sand, Clay, Red Bed
788 - 800' Anhydrite
800 - 3552' Shale & Lime
3552 - 3558' Shale
3558 - 3574' Lime & Shale
3574' - 3589' Lime
3589 - 3720' Shale
3720 - 3746' Lime & Shale
3746 - 4060' Lime
4060 - 4170' Shale, Lime, Chert, Sand
4170 - 4331' Chert, Lime
4331 - 4418' Sand
4418' RTD

ELEVATION:

FORMATION DATA

Anhydrite	788'
Heebner	3552'
Toronto	3574'
Douglas	3589'
Br. Lime	3720'
Lansing	3746'
Base K.C.	4060'
Marmaton	4069'
Conglomerate	4132'
Mississippi	4170'
Simpson	4331'
RTD	4418'

Surface Pipe: Set new 8-5/8"
23# pipe @286' w/200 sacks
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 2nd day of August 1984.

My Comm. Expires:

4-29-86.

Douglas M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 06 1984
CONSERVATION DIVISION
Wichita, Kansas