

15-151-21166-80-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 14 TWP. 26 RGE. 13 E/W
Location as in quarters or footage from lines:
NW NW SW

Lease Owner L. D. Davis
Lease Name Griffith Well No. B-1
Office Address Route 1, Box 183-B, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil & gas
Date Well Completed September 1982
Application for plugging filed 05-06-85
Plugging commenced 05-14-85
Plugging completed 05-16-85
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Non commercial
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Jack Luthi
Producing formation Arbuckle Depth to top 3890 bottom 3894 T.D. 4410
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface		0	350	8 5/8"	350	0
Production		0	4408	4 1/2"	4408	1890

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

05-14-85 Set plug at 3840', dumped 4 sacks of cement on top. Shot casing off at 2698',
could not pull. Shot off at 2599', could not pull casing. Shot off at 1890', pulled
50 joints 4 1/2" casing.

05-16-85 Halliburton pumped 300 pounds hulls, 10 sacks gel, pumped 50 sacks cement 60-
40-poz, pumped 10 sacks gel, pumped 100 pounds hulls, pumped 8 5/8" plug, pumped 10
sacks cement shut in. Max press. 600 pounds, shut in pressure.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor D. S. & W. Well Servicing, Inc. License #6901 5-28-85
MAY 28 1985

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
L. D. Davis (~~employee of owner~~ or (~~owner~~ or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) L. D. Davis
Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 85

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My Commission expires: 5-20-89

