


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 34 Twp. 29 Rge. 14W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NW SE NE

Lease Owner The Maurice L. Brown Company
Lease Name Bergner "A" Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed June 23 1979
Application for plugging filed (verbally) June 23 1979
Application for plugging approved (verbally) June 23 1979
Plugging commenced June 23 1979
Plugging completed June 23 1979
Reason for abandonment of well or producing formation

No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3900'

Set 1st plug at 510' with 50 sacks
2nd plug at 40' solid bridge with 12 sacks
rathole with 3 sacks

Cemented with 50/50 posmix, 6% gel.
Plug was down at 1:15 a.m., June 23, 1979

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1979
6-29-79
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jerry A. Langrehr, Executive Vice-Pres. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1979



My commission expires 8-21-82

Sherrie L. Brooks
Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Bergner "A" #1
 LOCATION: NW SE NE, Section 34-29-14
 Pratt County, Kansas
 SPUD DATE: June 13, 1979
 COMPLETION DATE: June 23, 1979

0	160	Sand
160	1000	Red bed
1000	1370	Red bed and shale
1370	1820	Shale and lime
1820	3437	Lime and shale
3437	3579	Shale and lime
3579	3900	Lime and shale
	3900	Rotary Total Depth

Spud hole at 11:00 a.m., June 13, 1979. Drilled 1000' of 12 1/4" hole. Ran 13 joints of new 8-5/8" - 28# casing. Set at 517' with 300 sacks of Halliburton lite, 3% Ca.Cl., 1/2# floccel per sack. Followed with 150 sacks of Class A cement, 3% Ca.Cl., 1/2# floccel per sack. Plug was down at 7:30 a.m., June 14, 1979.

T.D. 3900'. Set 1st plug at 510' with 50 sacks, 2nd plug at 40' solid bridge with 12 sacks, rathole with 3 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 1:15 a.m., June 23, 1979.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 29 1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice-President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Bergner "A" #1, NW SE NE, Section 34-29-14, Pratt County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jerry A. Langrehr
 Jerry A. Langrehr
 Executive Vice-President

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 27th day of June, 1979.

 SHERRIE L. BROOKS
 Sedgwick County, Ks.
 My Appt. Exp. 8-21-82

Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.