

1060130

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,773-00-00

C NE NW, Sec. 34, T 29 S, R 14 W/X

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Davis Well # 1

Operator: Texas Energies, Inc.
Name & P. O. Box 947
Address Pratt, KS 67124

County Pratt

Well Total Depth 4650 feet 151.12
Production

~~CHUCK~~ Pipe: Size 4 1/2 feet 4639

Surface Casing: Size 8 5/8 feet 494

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176 Chase, KS 67524

Company to plug at: Hour: 3:30p m Day: 19 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Norman Voth

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 1st plug pumped 35 sx cement to bottom with hole full of heavy mud. Shot pipe off at 3418'. 2nd plug pumped through swedge in sequence with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 120 cement. 3 sack hulls pumped just before the final 120 sx cement.

Signed Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 9:00 pm Day: 19 Month: January Year: 1984

ACTUAL PLUGGING REPORT 1st plug pumped 35 sx cement to bottom with hole full of heavy mud. Shot pipe off at 3418'. 2nd plug pumped through swedge in sequence with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 120 sx cement.

Remarks: Allied Cementing accomplished the cementing with 60/40 Poz with 2% gel and 3% cc. They recovered 3418' of production casing 4 1/2". Mr. Steve Durant gave the proposal. Paul A. Luthi was at well part of the plugging. They had pumped

3 sx hulls and 5 sx gel and the head blew off under 200# pressure. Luthi told them to get a new head welded on and finish plugging the well. Max pressure 1400# Shut in 700#.
I hereby certify that the above plugging instructions were given as herein stated

and that I (did / ~~did not~~) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
1-23-84
INVOICED
DATE 1-27-84 JAN 23 1984
WV. NO. 9280-6
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82