

1 010273

7-31-87

165R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,429-00-00

SW NE NW, SEC. 35, T 29 S, R 14 W

4290 feet from S section line

3630 feet from E section line

Lease Name Bergner Well # 1

County Pratt

Well Total Depth 4669 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

TECHNICIAN'S PLUGGING REPORT

Operator License #

Operator: Kansas Corporation Commission
Name & Address

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor KCC License Number

Address

Company to plug at: Hour: 10 a.m. Day: 31 Month: 7 Year: 19 87

Plugging proposal received from Jack Luthi

(company name) KCC (phone) 316-532-3593

were: 4 1/2" at 4669'

1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3' sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:50 a.m. Day: 31 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 4 sx cement on top of sand

2nd plug pumped 1 sx hulls, 10 sx gel and 50 sx cement at 3017' through
through bailer, 4 1/2" casing SDON. 10 joints 4 1/2" cemented in hole at 3017',

3rd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 550 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan; Recovered 2900' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

STATE CORP. COMMISSION
RECD
AUG 4 1987
8-4-87 Signed
CONSERVATION DIVISION
Wichita, Kansas

Jack L. Luthi
(TECHNICIAN)