

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-22084-00-00  
Spot: S2S2NWNE Sec/Twnshp/Rge: 36-18S-18W  
1080 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: HOLOPERIK Well #: 1  
County: RUSH Total Vertical Depth: 3948 feet

Operator License No.: 34625  
Op Name: WAUSAU DEVELOPMENT CORPORATI  
Address: 2300 HWY 11 NORTH  
LAUREL, MS 39440

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3390		WITH 2 SX CMT
CIBP		3500		
PROD	5.5	3945	1800	WITH 160 SX CMT
SURF	8.625	1163		WITH 600 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/20/2016 1:00 PM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: CIBP @ 3380' WITH 2 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 620' WITH 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. TOP OFF WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 01/20/2016 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 3390' WITH 2 SX CMT. 1ST PLUG AT 1250' WITH 50 SX CMT. 2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG AT 320' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3617	3620		
3438	3442		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED  
JAN 26 2016  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

JAN 29 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

Mo. 2.2.16