

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-21049-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 31-30S-15W  
301 feet from S Section Line, 4919 feet from E Section Line  
Lease Name: WALKER F Well #: 2  
County: BARBER Total Vertical Depth: 4851 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 124 N MAIN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	4725	430	WITH 175 SX CMT
SURF	8.625	400		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/06/2016 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP DOWN 2 7/8" CASING WITH 150# HULLS & 30 SX CMT. PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/12/2016 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 2 7/8" CASING WITH 150# HULLS & 30 SX CMT. DISPLACED CMT TO 4400'. (UNABLE TO FREE UP PRODUCTION CASING TO SPOT FIRST PLUG.) PERFORATE 2 7/8" AT 940'. 1ST PLUG PUMP DOWN CASING WITH 15 SX GEL & 50 SX CMT IN/OUT PERFS AT 940'. (SHOT CASING OFF AT 430' STILL HUNG UP BUT WORKED LOOSE.) SHUT DOWN. 1/11/16: 2ND PLUG SPOT 600# HULLS & 20 SX GEL. SHUT DOWN. 1/12/16: SPOT 5 SX GEL & 50# HULLS. BROKE CIRCULATION. SPOT 50 SX COMMON CMT W/4% CC. LET CMT SET FOR 2 HOURS. HOLE STAYED FULL. 3RD PLUG AT 60' WITH 40 SX CMT. PULLED OUT OF HOLE & TOP OFF SURFACE PIPE WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4618	4622		

Remarks: USED 60/40 POZMIX 4% GEL & COMMON CEMENT W/4% CC BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

SA

KCC WICHITA

JAN 20 2016

RECEIVED

RECEIVED  
JAN 15 2016  
KCC DODGE CITY

Form CP-2/3  
No  
2.2.16