

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24378-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 15-17S-11W
3040 feet from S Section Line, 4319 feet from E Section Line
Lease Name: HERTHEL Well #: 8
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: 314 5TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3362	0	125 SX
SURF	8.625	330	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2016 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GARY PAULEY Company: PAULEY, GARY DBA PAULEY OIL Phone: (785) 252-8024

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/800 # gel and 400 # hulls.
Well has packer cement in at 2810' with cement below packer.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 660' and 300'. Ran tubing to 2760' and pumped 8 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 660' and circulated cement to surface on casing w/70 sx cement. Closed valve on casing and circulated cement to surface on surface casing w/80 sx cement. Pulled tubing and topped off w/15 sx cement.

GPS: 38.57377 -098.53214

Perfs:

Top	Bot	Thru	Comments
3275	3285		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
Received _____ (TECHNICIAN) CM
KANSAS CORPORATION COMMISSION

JAN 17 2016

JAN 27 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

Handwritten signature/initials