

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20769-00-01
Spot: E2E2SE Sec/Twnshp/Rge: 24-34S-32W
1338 feet from S Section Line, 323 feet from E Section Line
Lease Name: HAAS Well #: 1-24 OWWO
County: SEWARD Total Vertical Depth: 5400 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5110		
PROD	5.5	5262	3183	WITH 270 SX CMT
SURF	8.625	1558		WITH 600 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2015 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4785' WITH 2 SX CMT. CIBP @ 4355' WITH 2 SX CMT. PLUG AT 1600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2015 3:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMPED BOTTOM WITH 35 SX CMT & 300# HULLS. PRESSURED UP TO 1500 PSI. TAGGED CMT AT 4200'. 1ST PLUG AT 1600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4832	4836		
4405	4410		


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed 

(TECHNICIAN)

RECEIVED
JAN 07 2016
KCC DODGE CITY 

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 19 2016
CONSERVATION DIVISION
WICHITA, KS

