

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-20929-00-01  
Spot: NESENE Sec/Twnshp/Rge: 28-29S-33W  
3411 feet from S Section Line, 411 feet from E Section Line  
Lease Name: MULL Well #: 3-28  
County: HASKELL Total Vertical Depth: 5650 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1750		
CIBP		4610		
DVT		3217		WITH 350 SX CMT
PROD	5.5	5454	0	WITH 580 SX CMT
SURF	9.625	1623		WITH 395 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/30/2015 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 1750'. LOAD HOLE, RUN CBL. PLUG AT 1700' WITH 50 SX CMT. PEFORATE AT 500'. PUMP CMT FROM 500'-0'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/30/2015 11:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 1750'. RAN CBL. CMT AT 1750'-1620, 1070'-530'. PERFORATE AT 500'.  
1ST PLUG AT 1705' WITH 35 SX CMT. 2ND PLUG AT 496'-0' WITH 187 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5285	5294		
5104	5108		
5096	5098		
5082	5085		
4924	4926		
4888	4896		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED  
JAN 07 2016  
KCC DODGE CITY

Signed

*[Signature]*  
*[Signature]*

(TECHNICIAN)  
KANSAS CORPORATION COMMISSION

JAN 19 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*702.2.16*