

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20624-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 2-20S-29W
3676 feet from S Section Line, 2296 feet from E Section Line
Lease Name: MURPHY Well #: 2
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 34911
Op Name: OIL KINGS, A GENERAL PARTNERSHIP
Address: 1578 COUNTY RD C
TRIBUNE, KS 67879

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4500 | | |
| DVT | | 2044 | | WITH 750 SX CMT |
| PROD | 4.5 | 4698 | 0 | WITH 325 SX CMT |
| SURF | 8.625 | 328 | | WITH 200 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2016 10:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: WILD WEST WELL SERVICE Phone: (620) 653-7368

Proposed Plugging Method: SPOT 30 SX CMT WITH HULLS ON BOTTOM. CIRCULATE CMT TO SURFACE FROM 2050'. PULL TBG & TOP OFF. PRESSURE BACKSIDE WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 01/26/2016 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4485' & SPOTTED 30 SX CMT WITH 200# HULLS. PULLED TBG TO 2045' & CIRCULATED CMT TO SURFACE WITH 150 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. PRESSURED BACKSIDE TO 200# WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4462 | 4465 | | |
| 4358 | 4364 | | |
| 4345 | 4348 | | |
| 4308 | 4310 | | |

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Eric MacLaren

RECEIVED
JAN 27 2016
KCC DODGE CITY

(TECHNICIAN)
KCC WICHITA

FEB 01 2016

RECEIVED

Form CP-2/3

NO
2-2-16