

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20234-00-00
Spot: N2 Sec/Twnshp/Rge: 29-32S-32W
3906 feet from S Section Line, 2564 feet from E Section Line
Lease Name: ALEXANDER PRATER Well #: 1
County: SEWARD Total Vertical Depth: 2715 feet

Operator License No.: 9262
Op Name: LOWRY EXPLORATION, INC.
Address: SUITE 306 427 S BOSTON AVE
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2570		WITH 2 SX CMT
PROD	5.5	2713	0	WITH 350 SX CMT
SURF	8.625	570		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/13/2016 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE BRADY Company: LOWRY EXPLORATION Phone: (918) 587-5094

Proposed
Plugging
Method:

CIBP @ 2570' WITH 2 SX CMT. PLUG AT 1630' WITH 40 SX CMT. PLUG AT 600'-0'. CHECK BACKSIDE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2016 3:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 2570' WITH 2 SX CMT. 1ST PLUG AT 1638' WITH 40 SX CMT. 2ND PLUG AT 602'-0' WITH 60 SX CMT. 15 SX CMT TO FILL UP. CHECK BACKSIDE WITH 5 SX CMT. BACKSIDE HEAD WAS CUT. COULDN'T PRESSURE UP.

Perfs:

Top	Bot	Thru	Comments
2605	2639		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
JAN 14 2016
KCC DODGE CITY

518

Received
KANSAS CORPORATION COMMISSION
JAN 19 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

10
2.2.14