

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-10085-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 6-31S-37W
2599 feet from S Section Line, 2467 feet from E Section Line
Lease Name: MCCLURE Well #: 1-6
County: STEVENS Total Vertical Depth: 2600 feet

Operator License No.: 9262
Op Name: LOWRY EXPLORATION, INC.
Address: SUITE 306 427 S BOSTON AVE
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	2600	2100	
PROD	7	2420	0	WITH 100 SX CMT
SURF	10	536		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/22/2016 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUG AT 1700' WITH 30 SX CMT. PLUG AT 1000' WITH 30 SX CMT & 200# HULLS. PLUG AT 570' WITH 90 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2016 1:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

Perfs:

1ST PLUG AT 1700' WITH 30 SX CMT & 300# HULLS. LOADED HOLE. STAYED FULL. 2ND PLUG AT 575'-0' WITH 100 SX CMT. CIRCULATED INSIDE & OUT.

Top	Bot	Thru	Comments
2420	2600		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY SARGENT LILLARD

Plugged through: TBG

District: 01

Signed [Signature]

RECEIVED
JAN 27 2016
KCC DODGE CITY [Signature]

Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

JAN 29 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

20-2-16