

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20301-00-01
Spot: S2N2SWSW Sec/Twnshp/Rge: 35-32S-31W
960 feet from S Section Line, 660 feet from W Section Line
Lease Name: GANO A Well #: 5
County: SEWARD Total Vertical Depth: 6020 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1750		
L1	4.5	4581		WITH 55 SX CMT
PROD	5.5	6019	0	WITH 275 SX CMT
SURF	8.625	1596		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/25/2016 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2016 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAGGED FILL UP AT 4940'. SPOT 40 SX CMT WITH 50# HULLS @ 4914' THROUGH TBG. NO RETURNS BUT FLUID LEVEL CAME UP FROM 2500' TO 800' FROM SURFACE. SET CIBP @ 1750'. TEST CASING ATO 700#. HOLDING. PERFORATE 4 HOLES AT 1648'. INJECTION RATE 2 BPM AT 150 PSI CIRCULATING OUT 5 1/2" X 8 5/8" ANNULUS. PUMP 25 SX CMT, THEN 20 7/8" BALL SEALERS & 25# HULLS IN 25 SX CMT. DISPLACE WITH 20 BBLS & PRESSURED TO 1000# LEAVING 25 SX CMT INSIDE THE CASING & 25 SX CMT OUTSIDE THE CASING. PERFORATE 4 HOLES AT 550'. CIRCULATE CMT TO SURFACE WITH 140 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5068	5078		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

RECEIVED
JAN 28 2016
KCC DODGE CITY

Signed

Ken Jehlik

51A

(TECHNICIAN)
KCC WICHITA

FEB 01 2016

RECEIVED

Ms. 2.14
Form CP-2/3