

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21875-00-01
Spot: SENESESW Sec/Twnshp/Rge: 34-30S-12W
676 feet from S Section Line, 2956 feet from E Section Line
Lease Name: HAAS Well #: 7
County: BARBER Total Vertical Depth: 4525 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3620		WITH 2 SX CMT
PROD	4.5	3732	1900	WITH 75 SX CMT
SURF	8.625	221		WITH 160 SX CMT

Well Type: SWD UIC Docket No: D26826.0 Date/Time to Plug: 01/27/2016 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L LOEB Phone: (620) 886-2419

Proposed Plugging Method: SET CIBP @ 3620' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2016 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3620' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 279' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3663	3665		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)
KCC WICHITA

RECEIVED
JAN 29 2016
KCC DODGE CITY

FEB 01 2016
RECEIVED

Form CP-2/3

no
2-2-16
CC-41C