

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21738-00-01
Spot: NWSENE Sec/Twnshp/Rge: 27-21S-34W
3760 feet from S Section Line, 990 feet from E Section Line
Lease Name: NUNN Well #: 11
County: FINNEY Total Vertical Depth: 4779 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3160		
CIBP		4300		WITH 2 SX CMT
DVT		3169		WITH 330 SX CMT
PROD	5.5	4779	0	WITH 150 SX CMT
SURF	8.625	1478		WITH 535 SX CMT

Well Type: EOR UIC Docket No: E30737.1 Date/Time to Plug: 01/05/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BRIAN MEYER Company: HARTMAN OIL Phone: (620) 272-1788

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2016 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4300' WITH 2 SX CMT. CIBP @ 3160' TO ISOLATE CASING LEAKS. TEST CASING TO 500#. HOLDING. RUN CBL FROM 1550' TO 30'. TOP OF GOOD CMT AT 1520' WITH SCATTERED CMT TO 1110'. PERFORATE 4 HOLES AT 1030'. INJECTION RATE 2 BPM @ 250 PSI. RUN TBG TO 1535' & SPOT A 50 SX CMT PLUG FROM 1535' TO 1030' IN THE 5 1/2" CASING. TOOH WITH TBG. CIRCULATE CMT FROM THE PERFS AT 1030' TO 0' USING 290 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4608	4614		
4362	4366		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JAN 07 2016
KCC DODGE CITY

Signed

SA

Ken Jehlik

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 25 2016

CONSERVATION DIVISION CP-2/3
WICHITA, KS

no 2-2-16 cc to me