

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-22828-00-01  
Spot: SENENE Sec/Twnshp/Rge: 4-7S-20W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DAVIS Well #: 1  
County: ROOKS Total Vertical Depth: 3679 feet

Operator License No.: 34903

Op Name: JASPAR CO.

Address: 1681 LIMESTONE ROAD SOUTH PO B  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3679		250 SX
SURF	8.625	217		185 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/14/2016 8:00 AM

Plug Co. License No.: 99977

Plug Co. Name: QUALITY OIL WELL CEMENTING

Proposal Rcvd. from: SHANE VEHIGE

Company: JASPAR COMPANY

Phone: (785) 623-6982

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement.  
Port Collar at 1781' w/650 sx cement.  
Casing leak at 1430' - 1450'.  
Production perforations: 3375' - 3655'.  
Tubing stuck in hole at 2140'.  
Rods stuck in hole at 1710'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/14/2016 11:30 AM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2120' and pumped 80 sx cement. Pulled tubing to 1433' and pumped 100 sx cement to circulate cement to surface. Pulled tubing to surface. Hooked to 4 1/2" casing and pumped 15 sx cement w/500 psi. Removed swedge and topped off 4 1/2" casing w/5 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 1/8 bbl water. Shut in pressure 300 psi.

GPS: 39.47556N -099.54811W

Perfs:

Top	Bot	Thru	Comments
3653	3655		
3641	3646		
3557	3557		
3543	3543		
3476			
3470			
3428	3432		
3394	3397		
3377			
3375	3378		
3365			

Remarks: QUALITY OILWELL CEMENTING TICKET # 1506

Plugged through: TBG

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JAN 27 2016

2-27-16

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*No 2-2-16*

JAN 14 2016