

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-02223-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 2-17S-10W  
2310 feet from S Section Line, 660 feet from E Section Line  
Lease Name: PHELAN Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3295 feet

Operator License No.: 7757  
Op Name: FOLK, MAX LEE DBA FOLK OIL  
Address: 604 N. BISMARCK AVE  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4	3160		
PROD	4	3269		75 SX
SURF	7	255		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2015 9:00 AM  
Plug Co. License No.: 34032 Plug Co. Name: SIEMSEN WELL SERVICE INC.  
Proposal Rcvd. from: MIKE FOLK Company: FOLK OIL Phone: (620) 200-5123

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/22/2015 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 3160' AND CAP WITH 3 SX'S CEMENT.  
PERFORATE AT 1300', 950', AND 305'. RUN TUBING TO 1300' AND PUMP 4 SX'S GEL  
FOLLOWED BY 35 SX'S CEMENT. PULL TUBING UP TO 950' AND WAIT 1 HOUR.  
TAG CEMENT WITH TUBING @ 1044'. PULL TUBING TO 950' AND PUMP 35 SX'S,  
PULL TUBING TO 305' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING  
OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3269	3284	OH	

Remarks: LOG TECH OF KS. #8655. ALLIED TICKET 365745. TA - N.O.V. LETTER WAS SENT ON THIS WELL.

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

KCC WICHITA

JAN 19 2016

RECEIVED

Form CP-2/3

*no 2.2.16*

*18*