

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21568-00-00
Spot: SWSW Sec/Twnshp/Rge: 23-29S-32W
678 feet from S Section Line, 4681 feet from E Section Line
Lease Name: HESKAMP Well #: 2-23
County: HASKELL Total Vertical Depth: 5758 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5050		WITH 2 SX CMT
PC		3000		
PROD	5.5	5757	0	WITH 800 SX CMT
SURF	8.625	1815		WITH 775 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/12/2016 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: CIBP @ 5050' WITH 2 SX CMT. PLUG AT 1830' WITH 25 SX CMT. PLUG AT 700' TO 0' WITH 75 SX CMT. BRING 75 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2016 2:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5050' WITH 2 SX CMT. 1ST PLUG AT 1829' WITH 25 SX CMT. 2ND PLUG AT 690' WITH 75 SX CMT. TOPPED OFF WITH 15 SX CMT. PUMPED 0 SX CMT DOWN BACKSIDE. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
5515	5526		
5279	5284		
5109	5119		
4660	4668		
4278	4294		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed SA

RECEIVED
JAN 14 2016
KCC DODGE CITY

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 19 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no 2-2-16