

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20531-00-01  
Spot: NW Sec/Twnshp/Rge: 29-24S-40W  
4469 feet from S Section Line, 4082 feet from E Section Line  
Lease Name: WOOD Well #: 5A-29  
County: HAMILTON Total Vertical Depth: 5250 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2378	0	WITH 575 SX CMT
SURF	8.625	1395		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2016 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 50 SX CMT WITH 250# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1700'. PRESSURE UP & TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS NECESSARY

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/26/2016 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT WITH 200# HULLS TO 2344'. DISPLACE CMT TO 1600'. PRESSURE TEST CASING TO 500#. HOLDING. RUN CBL FROM 1400' TO 100'. TOC BEHIND 4 1/2" CASING IS 1246'. PERFORATE 4 HOLES AT 600'. RUN TBG TO 1482' & CIRCULATED CMT FROM 1482' TO 0' IN THE 4 1/2" CASING AND FROM 600' TO 0' IN THE 4 1/2" X 8 5/8" ANNULUS USING 190 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2334	2335		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

*[Signature]*  
5A

(TECHNICIAN)

KCC WICHITA

FEB 01 2016

RECEIVED

RECEIVED  
JAN 28 2016  
KCC DODGE CITY

*[Signature]*

Form CP-2/3

*no 2-2-16*