

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23717-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 11-7S-22W
470 feet from N Section Line, 1900 feet from E Section Line
Lease Name: WHITE Well #: 1
County: GRAHAM Total Vertical Depth: 3820 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3819		470 SX
SURF	8.625	219		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAN WINDHOLZ Company: BLACK DIAMOND OIL, INC. Phone: (785) 259-8403

Proposed Plugging Method: Ordered 465 sx 60/40 pozmix 4% gel cement, 14 sx gel spacer and 300 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2015 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 75 sx cement w/200 # hulls followed by 14 sx gel spacer. Pumped 300 sx cement and topped off with 55 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 35 sx cement. Shut in pressure 300 psi.

GPS: 39.46528N -099.73875W

Perfs:

Top	Bot	Thru	Comments
3740	3744		

Remarks: ALLIED CEMENTING TICKET # 55090

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JAN 27 2016

1-27-16

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

720
2-2-16