

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00029-00-01  
Spot: NENESW Sec/Twnshp/Rge: 21-22S-33W  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: DAMME Well #: 1  
County: FINNEY Total Vertical Depth: 4737 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		
PROD	5.5	4657	0	WITH 150 SX CMT
SURF	8.625	350		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2016 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO LLC Phone: (316) 722-8650

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2016 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF 2 3/8" TBG FISH AT 3337'. TOP OF ROD FISH @ 4324'. HAS GLORIETTA LEAK. SET CIBP @ 1100' OVER GLORIETTA CASING LEAK. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 1075'. INJECTION RATE 3 BPM @ 700#. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT. DISPLACE TO 700' @ 800 PSI LEAVING 40 SX CMT INSIDE THE CASING & 40 SX CMT OUTSIDE THE CASING. NO CIRCULATION UP SURFACE CASING. PERFORATE 4 HOLES @ 400'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4657	4727	OH	
4645	4652		
4417	4466		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed *Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
JAN 21 2016  
KCC DODGE CITY *MD*

KCC WICHITA

FEB 01 2016

RECEIVED

Form CP-2/3

*no 2.2-16*