

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21164-00-00
Spot: SESESE Sec/Twnshp/Rge: 20-22S-33W
320 feet from S Section Line, 281 feet from E Section Line
Lease Name: ROSALIE Well #: 1-20
County: FINNEY Total Vertical Depth: 5000 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4610		WITH 2 SX CMT
PROD	5.5	4999	1795	WITH 175 SX CMT
SURF	8.625	1760		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2016 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2016 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4610' WITH 2 SX CMT. PUMP 50 SX CMT W/3% CC & 250# HULLS AT 1845'. NO CIRCULATION. PULL TBG UP ABOVE TOC & ATTEMPT TO LOAD HOLE WITH 10 BBLs. COULD NOT. WAIT 3 1/2 HOURS & TAG TOC @ 1745' WITH TBG. PULL TO 1135' & SPOT 50 SX CMT. FULL CIRCULATION. PUMP 20 SX CMT AT 60'. FULL CIRCULATION.

Perfs:

Top	Bot	Thru	Comments
4712	4725		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
JA (TECHNICIAN)
KCC WICHITA

RECEIVED
JAN 21 2016
KCC DODGE CITY

FEB 01 2016
RECEIVED

Form CP-2/3
no 2-2-16