

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20083-00-02
Spot: SWNESENE Sec/Twnshp/Rge: 25-32S-31W
3458 feet from S Section Line, 584 feet from E Section Line
Lease Name: STEWART Well #: 2
County: SEWARD Total Vertical Depth: 5946 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1062		WITH 2 SX CMT
CIBP		1325		
PROD	5.5	5634	0	WITH 350 SX CMT
SURF	8.625	1360		WITH 600 SX CMT

Well Type: SWD UIC Docket No: D23334.0 Date/Time to Plug: 01/07/2016 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed
Plugging
Method:

CIBP @ 1062' WITH 2 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL
Date/Time Plugging Completed: 01/07/2016 2:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 1062' WITH 2 SX CMT. RAN CBL. FOUND CMT TO SURFACE. RAN TBG TO 996'. CIRCULATED CMT TO SURFACE WITH 100 SX CMT. TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5570	5573		
5550	5553		
5524	5529		
5517	5520		
5498	5501		
4671	4676		
1112	1212		


Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
JAN 14 2016
KCC DODGE CITY

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 19 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

NO
2-2-16
CC to UIC